

Табеларни приказ количине радова по профилима осе 2 (пешачка стаза/канали/асфалт)																	
Sect.	Stat Dist.	PLANIRANJE I VALJANJE POSTELJICE [m/m²]	Dist.	NABIJANJE PODTLA [m/m²]	Dist.	DKA31 STAZA [m²/m³]	Dist.	PESAKSTAZA [m²/m³]	Dist.	ISKOP ISPOD PS [m²/m³]	Dist.	ISKOP KANALA [m²/m³]	Dist.	HUMUSIRANJE KANALA [m²/m³]	Dist.	IZRAVNAVAJUCI SLOJ [m²/m³]	Dist.
P1	0+2.24	0		0		0		0		0		0		0		0.153	
	9.93	146.517	9.93	146.517	9.93	21.287	9.93	29.118	9.93	25.814	9.93	0	0	0	0	1.887	9.93
P2	0+12.17	29.51		29.51		4.287		5.865		5.199		0		0		0.227	
	1.45	43.903	1.45	43.903	1.45	6.386	1.45	8.723	1.45	8.591	1.45	0	0	0	0	0.335	1.45
P3	0+13.62	31.045		31.045		4.52		6.167		6.65		0		0		0.235	
	11.38	205.804	11.38	205.8	11.38	29.345	11.38	40.92	11.38	45.584	11.38	17.821	11.38	9.654	11.38	1.949	11.38
P4	0+25.00	5.124		5.123		0.637		1.025		1.361		3.132		1.697		0.107	
	3.67	17.774	3.67	18.506	3.67	2.303	3.67	3.605	3.67	4.881	3.67	8.801	3.67	4.683	3.67	0.326	3.67
P5	0+28.67	4.562		4.962		0.618		0.94		1.299		1.664		0.856		0.07	
	4.75	23.003	4.75	23.953	4.75	2.981	4.75	4.666	4.75	6.065	4.75	7.876	4.75	5.918	4.75	0.206	4.75
P6	0+33.42	5.124		5.124		0.637		1.025		1.255		1.652		1.636		0.016	
	6.4	30.99	6.4	30.987	6.4	10.904	6.4	6.198	6.4	7.636	6.4	10.361	6.4	7.807	6.4	0.052	6.4
P7	0+39.82	4.561		4.56		2.77		0.912		1.131		1.586		0.804		0	
	10.18	49.293	10.18	49.285	10.18	17.342	10.18	9.858	10.18	11.969	10.18	16.98	10.18	12.344	10.18	0	0
P8	0+50.00	5.124		5.123		0.637		1.025		1.22		1.75		1.621		0	
	13.21	68.676	13.21	67.545	13.21	8.392	13.21	13.511	13.21	16.991	13.21	22.256	13.21	15.974	13.21	0	0
P9	0+63.21	5.274		5.103		0.634		1.021		1.352		1.62		0.797		0	
	11.79	61.24	11.79	60.232	11.79	7.48	11.79	12.047	11.79	16.246	11.79	19.365	11.79	9.523	11.79	0	0
P10	0+75.00	5.115		5.114		0.635		1.023		1.404		1.665		0.818		0	
	6.89	34.698	6.89	34.697	6.89	11.594	6.89	6.663	6.89	9.187	6.89	5.737	6.89	2.82	6.89	0	0
P11	0+81.89	4.957		4.957		2.73		0.911		1.263		0		0		0	
	8.35	41.988	8.35	41.988	8.35	14.044	8.35	8.063	8.35	10.05	8.35	6.425	8.35	3.318	8.35	0	0
P12	0+90.24	5.1		5.1		0.634		1.02		1.144		1.539		0.795		0	
	1.83	9.605	1.83	9.605	1.83	1.169	1.83	1.921	1.83	2.209	1.83	2.748	1.83	1.477	1.83	0	0
P13	0+92.07	5.398		5.398		0.644		1.08		1.27		1.465		0.819		0	
	0.61	3.284	0.61	3.292	0.61	0.393	0.61	0.659	0.61	0.777	0.61	0.891	0.61	0.492	0.61	0	0
P14	0+92.68	5.369		5.397		0.644		1.079		1.276		1.456		0.795		0	
	7.32	39.369	7.32	39.51	7.32	5.24	7.32	7.901	7.32	9.538	7.32	5.328	7.32	2.911	7.32	0.01	7.32
P15	0+100.00	5.387		5.398		0.788		1.079		1.33		0		0		0.003	
	10.59	57.126	10.59	57.182	10.59	7.587	10.59	11.435	10.59	14.442	10.59	7.307	10.59	4.249	10.59	0.591	10.59
P16	0+110.59	5.402		5.402		0.645		1.08		1.398		1.38		0.802		0.109	
	1.85	9.851	1.85	9.851	1.85	1.194	1.85	1.954	1.85	2.392	1.85	2.71	1.85	1.612	1.85	0.255	1.85
P17	0+112.44	5.248		5.248		0.646		1.032		1.188		1.549		0.94		0.167	
	2.04	10.863	2.04	10.863	2.04	1.322	2.04	2.154	2.04	2.606	2.04	3.003	2.04	1.823	2.04	0.306	2.04
P18	0+114.48	5.402		5.402		0.65		1.08		1.366		1.395		0.848		0.133	
	7.29	39.447	7.29	39.378	7.29	4.721	7.29	7.876	7.29	9.269	7.29	9.924	7.29	6.077	7.29	0.86	7.29
P19	0+121.77	5.421		5.402		0.645		1.08		1.177		1.328		0.82		0.103	
	3.23	17.127	3.23	17.19	3.23	5.461	3.23	3.304	3.23	3.898	3.23	4.22	3.23	2.683	3.23	0.28	3.23
P20	0+125.00	5.184		5.242		2.737		0.966		1.237		1.285		0.841		0.07	
	25	128.825	25	129.549	25	42.168	25	24.87	25	35.686	25	26.82	25	31.183	25	3.168	25
P21	0+150.00	5.122		5.122		0.637		1.024		1.618		0.86		1.653		0.183	
	17.69	364.696	17.69	364.696	17.69	52.777	17.69	72.149	17.69	77.046	17.69	7.61	17.69	14.623	17.69	2.816	17.69
P22	0+167.69	36.11		36.11		5.33		7.133		7.093		0		0		0.135	
	7.31	155.118	7.31	155.118	7.31	22.283	7.31	30.698	7.31	31.457	7.31	3.024	7.31	3.154	7.31	1.645	7.31
P23	0+175.00	6.33		6.33		0.766		1.266		1.514		0.827		0.863		0.315	
	8.49	26.87	8.49	26.87	8.49	3.254	8.49	5.374	8.49	6.426	8.49	3.512	8.49	3.663	8.49	2.771	8.49
P24	0+183.49	0		0		0		0		0		0		0		0.338	
	1.88	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.409	1.88
P25	0+185.37	0		0		0		0		0		0		0		0.097	
Sume:		1586.067 PLANIRANJE I VALJANJE POSTELJICE [m²]		1586.516 NABIJANJE PODTLA [m²]		279.626 DKA31 STAZA [m³]		313.666 PESAKSTAZA [m³]		358.757 ISKOP ISPOD PS [m³]		192.719 ISKOP KANALA [m³]		145.986 HUMUSIRANJE KANALA [m³]		17.865 IZRAVNAVAJUCI SLOJ [m³]	